vi. Brick work should be ensured that a proper bond is maintained throughout the work.

vii. The bricks should be laid on a full bed of mortar. The frog in the brick should be at the top and filled with mortar to ensure proper bonding.

viii. Scaffolding should be adopted for construction at higher level.

ix. All the course should be laid truly horizontal and all the vertical joints should be truly vertical. The verticality should be checked with plumb bob.

x. All the finished masonry work should be kept wet for at least seven days.



ACTIVITY 7

Prepare an album of rich heritage monuments and temples situated in India.

6.3.6. Thickness of Brick Wall

Thickness of brick wall is decided by considering the following:

1. The total load acting on the walls.
2. The total height of the wall.
3. The quality of materials used for the construction of wall.
4. The length of the wall.
5. The height between one floor to the other.

Formula to find the thickness of wall is:

$$A = \frac{P}{O}$$

$$T \times L = \frac{P}{O}$$

$$\text{Thicknes of wall 'T'} = \frac{P}{L \times O}$$

Where,

P = Total load on the wall

A = Area of the wall

L = Length of the wall

T = Thickness of the wall

O = Permissible bearing capacity

Civil_English_Unit_6.indd 150 12/21/2019 4:40:03 PM